SECTION 00 11 01
ADVERTISEMENT FOR BIDS

Huerfano County Water Conservancy District
La Veta, Colorado

General Notice

The Huerfano County Water Conservancy District (HCWCD, Owner) is requesting Bids for the construction of the following Project:

Sheep Mountain Augmentation Facility Liner Ballast Repair Project

Bids for the construction of the Project shall be submitted **via electronic means** to **BOTH** stevesmith@applegategroup.com **and** weshogan@applegategroup.com, by **November 16th, 2026** at **5PM** local time. At that time the Bids received will be privately opened and read.

Summary of Work:

Work includes installing a 12-inch thick layer of new ballast material across the upper reservoir slopes, consisting of imported 6-inch D50 angular rip rap. Work also includes localized repair of exposed geotextile, placement of ¾-inch bedding material beneath the riprap (6 inches thick over areas of geotextile repair and 3 inches thick elsewhere), and protection of the existing geomembrane liner during construction. Work also includes repair of any damage found in the existing 45-mil reinforced polypropylene (RPP) geomembrane liner, paid on a unit price basis. Bidders shall include a geomembrane repair subcontractor with RPP repair experience and shall identify that subcontractor in the Bid. Riprap and bedding material will be stockpiled on site by Owner prior to the work described herein, and bidders will not need to furnish riprap or bedding. Site reclamation of disturbed areas is included in the work. Work includes the approximate quantities for significant work items (Bid Sheet in the Bid Form provides comprehensive quantities to be bid on):

- 8,680 SF of geotextile repair
- SF unit cost for geomembrane repair (assumed no damage; actual quantity will depend on the damage found)
- 3,220 CY of 6-inch diameter riprap to be placed
- 810 CY of ¾-inch bedding material to be placed below the riprap
- 170 CY of ¾-inch bedding material to be placed over geotextile repair areas

Work is anticipated to begin on Monday, January 4th, 2027. Reseeding will be performed in spring 2027.

Domestic Preference

This project is subject to the Build America, Buy America Act (BABAA) requirements under Title IX of the Infrastructure Investment and Jobs Act (IIJA), Pub. L. 117-58, §§ 70901-70953. Absent an approved waiver, all iron, steel, manufactured products, and construction materials used in this project must be produced in the United States.
The following waivers apply to this Contract:
BABAA De Minimis, Small Grants, and Minor Components

Obtaining the Bidding Documents

Information and Bidding Documents for the Project can be obtained by emailing:
weshogan@applegategroup.com

Pre-bid Conference

A mandatory pre-bid conference for the Project will be held on **Thursday, October 29th, 2026** from **2 PM – 4 PM** at **Sheep Mountain Augmentation Facility (SMAF)** off of CO RD 550 in La Veta, CO (Approx. Coordinates 482060.55 E, 4181111.35 N)

Bids will not be accepted from Bidders that do not attend the mandatory pre-bid conference. The pre-bid meeting will be held outside and followed by a site tour. In order to reduce the number of people present at the meeting, please minimize personnel attending from each company.

Questions

All Questions regarding this solicitation shall be emailed by no later than 5 PM MST on **Friday, November 6th, 2026**. Questions will be answered before end of day **Tuesday, November 10th, 2026**.

Instructions to Bidders

For all further requirements regarding bid submittal, qualifications, procedures, and contract award, refer to the Instructions to Bidders that are included in the Bidding Documents.